

Riverside Phase 3 — Technical Due Diligence

Contoso Group — Confidential — 15 March 2026

Riverside Phase 3 — Technical Due Diligence

Prepared by Group Engineering with input from external consultant Apex Building Sciences.

1. Geotech & Civil

Site sits on river-terrace alluvium; bearing capacity 180-220 kPa at 4-6m depth. Bored-pile foundations recommended for towers; raft foundations for low-rise. No active fault lines within 12 km. Flood study (Apex, Feb 2026) confirms 1-in-100yr level is 1.4m below proposed finished-floor level.

2. MEP & Building Services

Power: 22kV connection from city grid via two new substations (4MVA + 6MVA). Standby gensets for life-safety only. Water: dual-source from city potable supply with on-site 2,400m³ tank for 24h emergency supply. Drainage discharges to upgraded city storm system.

3. Sustainability

LEED Gold targeted for office tower (registered); residential blocks designed to local code +15%. PV-ready roofs (peak 1.2MW). Water recycling for landscape (target 35%). Construction waste recycled target 75%.

4. Building Code Compliance

Code area	Status	Notes
City zoning	Approved	Mixed-use within plan envelope
Building height	Approved	Tower 1: 28 floors (95m). Within district maximum 120m.
Fire safety	Approved	Sprinklered throughout; pressurised stairwells; smoke-extract
Accessibility	Approved	ADA-compliant (or local equivalent); routes audited
Permitting	1 open	Final clarification on parking provision — resolution 7 Apr

5. Construction Programme

Three-tower critical path: substructure 9 months, superstructure 18 months, finishes & MEP 12 months (overlapping). Total programme to handover: 39 months. Buffer 3 months.

6. Recommendations

- Lock in pile-rig contractor by end Q2 — single-source risk noted.
- Pre-purchase curtain-wall package by Q3 to fix metallic-finish pricing.
- Confirm parking provision clarification ahead of site mobilisation.
- Budget 6.2% contingency on remaining build cost — appropriate for project complexity.